BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/04/2019-20 Date: 12.06.2019

Indet No: BBMP/2018-19/OW/WORK_INDENT34925/CALL-2

SCHEDULE -B

Name of Work: Maintenance of Park in Jalahalli ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	700.00	SITE /JUNGLE CLEARENCE: Cutting and clearing thin jungle including removal of roots with a intitial lead of 50 m and life of 1.50 m and General Cleaning: Removal of dried leaves, solid waste and cleaning of the area	Sqm	9.00	Rupees Nine Only
2	200.00	Shrubs in Groups Developing the area for shrubs by digging to a depth of 0.45m, filling 50% with sand [0,0375 Cum], FYM [0.075 Cum], Red earth [0.21], [I.e. in the proportion of 1:2:3] and planting with well established plants (8 plants per sq mtr) exclusive of cost of plants and inclusive of ingredients	Sqm	456.00	Rupees Four Hundred Fifty Six Only
3	200.00	Shrubs in Groups Cost of the Plant (8 Plants per Sqm) including Transportation and Handling Charges	Sqm	630.00	Rupees Six Hundred Thirty Only
4	30.00	Planting of specimen plants Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0,021 Cum) (i.e. in the proportion of 1:2:3) and planting of Ficus Benjimina Prestige (90cm - 150cm ht) / Ficus Benjimina starlight(90cm - 150cm ht) Ficus Benjimina Black(90cm - 150cmm ht) / Ficus Nuda / mini luccii (90cm - 150cm ht) / Ficus Panda (90cm - 150cmm ht) ht) Ficus traingularis Including cost of plant, materials, transporation and handling & planting Cost)	Each	2621.00	Rupees Two Thousand Six Hundred Twenty One Only
5	20.00	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0,021 Cum) (i.e. in the proportion of 1:2:3) and planting of Plumeria Alba / Rubra (150cm - 240cm ht) Pulmeria Rubra (150cm - 240cm ht) Including cost of plant, materials, transporation and handling & planting Cost)	Each	3145.00	Rupees Three Thousand One Hundred Forty Five Only
6	43.00	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0,021 Cum) (i.e. in the proportion of 1:2:3) and planting of Bambusa Ventricosa (90 - 120 cm ht) Bambusa Vulgaris (150cm - 240cm ht) Bamboo Varigated (120cm - 150cm ht) Including cost of plant, materials, transporation and handling & planting Cost)	Each	1258.00	Rupees One Thousand Two Hundred Fifty Eight Only
7	100.00	Supplying of Red Soil (New Earth Filling) Supply of Good Quality Red Soil for Gardening and Growing of Plants, Shrubs, Etc., Including the % weightage given to B.B.M.P. Area.	cum	460.00	Rupees Four Hundred Sixty Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

8	8.00	Sprinkler System: Providing and fixing of sprinkler system with in the site by using 25mm/10kg,40mm/6kg, 50mm/6kg good quality PVC pipes,ISI marked sprinklers, control valves and fitiings etc, Including excavation and back filling trenches. (Excluding of Providing Borewell , Electrification & pump). As per the specification and direction of the concerned officer. Rates may be quoted as per data rate specific to the field condition.	Each	4193.00	Rupees Four Thousand One Hundred Ninety Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner